terrain design studio
architects & interior designers

6th May 2025

To,
Mr. Aniket Deotale ji
Nagpur.

Sub: Offer for **Architectural Turn-Key work** for your Residential building at Nagpur.

Dear Sir,

We thank you for offering us to quote for Architectural turnkey work for your residential building in Nagpur.
The schedule of services to be provided is given as follows:

A) CONSULTANCY

- **CONCEPT DESIGN [STAGE 1]**
  Ascertain Client's requirements, examine site constraints & potential; and prepare a design brief for Client's approval.

- **PRELIMINARY DESIGN AND DRAWINGS [STAGE 2] :**
- Modify the conceptual designs incorporating required changes and prepare the preliminary drawings, sketches, study model, etc., for the Client's approval along with preliminary estimate of cost on area basis.

- **DRAWINGS FOR CLIENT'S/ STATUTORY APPROVALS [STAGE 3] :**
  Prepare drawings necessary for Client's/ statutory approvals and ensure compliance with codes, standards and legislation, as applicable and get the Client the statutory approvals thereof, if required

- **ELEVATION DESIGN AND 3D [STAGE 4] :**

Designing elevation of the building to suits the site and clients brief. Also preparation of computerized 3D rendered image.

- **WORKING DRAWINGS [STAGE 5] :**
  Prepare working drawings, specifications and schedule of quantities sufficient to prepare estimate of cost including code of practice covering aspects like mode of measurement, method of payments, quality control procedures on materials & works and other conditions of contract.

- **CONSTRUCTION [STAGE 6] :**
  - Prepare and issue working drawings and details for proper execution of works during construction.
  - Coordinate with structural designer for issues related to R.C.C details.
  - Approve samples of various elements and components.
  - Visit the site of work, at intervals mutually agreed upon, to inspect and evaluate the Construction Works and where necessary clarify any decision, offer interpretation of the drawings/specifications.
  - Issue two sets of as built drawings including services and structures.

Please refer to our schedule of specifications and schedule of financial details for further information.

Please feel free to call us for any clarifications. We assure you of quality work and best services.
Thanking You,



terrain design studio
Ar. Pankaj Kriplani & Ar. Nikita Kriplani

Office address – A4, First Floor, Khullar Apartment, Byramji Town, Nagpur-440013
Mob. No.: +91 8087088948, email id:prk@terraindstudio.com

B) **SPECIFICATIONS**

Sr.No	Item	Specification	Type A	Type B	Type C
1	Excavation	Excavation will be done till a depth 10' from natural ground level or till hard soil is achieved or as per bearing capacity required by the structural designer.	as per site condition	as per site condition	as per site condition
2	Reinforcement	FE 500 rolled steel of TMT/ make or equivalent of ISI approved make to be used in proportion as specified by structural designer.	Raipur/Buland/Primegold	Lodha/Sangam	Kamdhenu/jsw/Sail
3	Cement	53 Grade PPC Cement to be used as per availability	Janghrodhak/ Dalmia/JK Laxmi	Birla Chetak/MP Birla/Birla Shakti	Ultratech/ACC/ Ambuja
4	RCC in Foundation	M20 or M25 mix design to be used as specified by structural designer. Open foundation to be proposed. Foundation to be designed proposed structure + one floor for future provisions.	as per Drawing	as per Drawing	as per Drawing
5	Back Filling	Backfilling till average ground level will be done with excavated material available at site. To increase the plinth level fly ash will be used as approved by structural designer.	Fly ash	Fly ash	Fly ash
6	Anti-Termite	Anti-termite treatment chemical shall be used before plinth slab casting	Certified chemical	Certified chemical	Certified chemical

7	RCC in columns	M20 or M25 mix design to be used as specified by structural designer. Open foundation to be proposed. Foundation to be designed proposed structure + one floor for future provisions.	as per Drawing	as per Drawing	as per Drawing
8	Plinth Level	Average Ground Level will be 1’6” from Road Level in front of road.And plinth level 2'6" from Road Level	avg. GL-1'from RL avg.PL-2' from RL	avg. GL-1'6" from RL avg.PL-2'6" from RL	avg. GL-1'6" from RL avg.PL-3' from RL
9	RCC in beams	M20 or M25 mix design to be used as specified by structural designer	as per Drawing	as per Drawing	as per Drawing
10	RCC in slabs	M20 or M25 mix design to be used as specified by structural designer	as per Drawing	as per Drawing	as per Drawing
11	Brickwork	brickwork will be done with AAC blocks/Fly ash/Red Bricks with cement mortar Or Bricks wall as recommended by structural engineer (Outer wall 9” and Inner wall 4.5”)	Fly ash Bricks	Red Bricks	AAC Block/Red Bricks
12	Lintel level	Lintel level of doors and windows	7' height	8' height	8' height
13	Slab Height	Floor to floor height	10' height	10' 6" height	11' height
14	External plaster	Single coat plaster of thickness approx. 15mm to be done in cement and sand in the ratio of 1:4.	Single coat	Single coat	Double Coat /Punch plaster
15	Internal plaster	12mm thick cement plaster to be done on all walls	Single coat	Single coat	Single coat
16	Waterproofing	Waterproofing by using brickbat coba, grouting and chemical compound method to be done for all toilets and terraces and lift Pit. Chemical compound coating to be done and IPS Work for balconies.	Only Toilet/Balcony/ Utility area	Only Toilet/Balcony/ Utility area	Only Toilet/Balcony/ Utility area
17	Terrace level	Parapet wall as per design, to be provided	Brickwork /MS Railing	Brickwork /MS Railing	Brickwork /MS Railing

18	Main Staircase	Staircase to be provided till the terrace level with SS railing	SS Railing	SS Railing	SS Railing
19	Railing in Elevation	Provision for Toughened Glass and SS and MS railing to be provided for balconies.	MS Railing	SS Railing	Glass Railing
20	Fabrication work	Fabrication work required as per elevation for covering drainage pipes	No	No	yes
21	Compound wall	9” thick, 6’ hight compound wall with two gates to be provided	as per Drawing	as per Drawing	as per Drawing
22	UG Tank	Under ground water tank in R.C.C. to be provided as required Quantity.	as per required Quantity	as per required Quantity	as per required Quantity
23	Overhead water tank	RCC water tank/Syntex (Plasto) be provided as required	as per required Quantity	as per required Quantity	as per required Quantity
Plumbing Work					
24	Plumbing pipes & Fittings	All internal plumbing will be done in CPVC Pipe fittings of Supreme Company, vertical sewer lines in SWR, and underground piping in Double layered PVC pipes.	Supreme	Supreme	Ashirwad/Astral
25	Plumbing chambers	PVC/Brickwork underground chambers to be used wherever required.	as per site condition	as per site condition	as per site condition
26	Sanitary Fittings	Jaquar or equivalent make fiitings to be used. Metropol, Double Function divertor, Single function wall mount shower.	Jaguar-Essco	Jaguar	Jaguar
27	Sanitary ware	Jaquar/Simpolo or equivalent.	Simpolo/Escco	Jaguar	Jaguar
28	Water tank sensor	Provision for water tank sensor to be done to avoid manually filling the tank every day.	No	Yes	Yes
Electrical Work					

29	Internal electrification	KEI/RR/Finolex/Polycab wires, Legrand/Gold medal switches, L&T/Hagger MCBs to be used. Wall lights points to give 100 lux level, provisions for TV, AC,Inverter in all rooms to be provided.	Drawing room -03,Bedroom-04,toilet -02,Parking-02,Kitchen -03,Utility area -01,Balcony-01	Drawing room -04,Bedroom-04,toilet -02,Parking-03,Kitchen -03,Utility area -02,Balcony-01	Drawing room -05,Bedroom-04,toilet -02,Parking-02,Kitchen -04,Utility area -02,Balcony-01
30	External electrification	Compound wall light points, gate column light points and basic electrification for ceiling lights for parking area	wall compund -02,parking area -02	wall compund -04,parking area -04	wall compund -06,parking area -06
Flooring and Dado					
31	Entrance Ramps	Granite Entrance Ramps and steps to be provided in front of gates	Granite	Granite	Granite
32	Parking area	Parking tile to be provided for flooring of parking area	400X400 Size	400X400 Size	600X600 Size
33	Flooring Tiles	Digital vitrified flooring tiles of following size to be laid.	600x600 Size	600x1200 Size	800x1600 Size
34	Master Bedroom Flooring	Wooden Tile and flooring for master bedroom	Wooden Tile	Wooden Tile	Wooden Floor
35	Toilet Wall Tiles	Vitrified/ceramic tiles of size (2'x4') to be laid.	300x600 Size	600x1200 Size	600x1200 Size
36	Kitchen Otta	Otaa to be used and Wall Tile above kitchen otta	Otta-Granite , wall tile -300x600	Otta-full body tile wall tile -600x1200	Otta-Quatz stone wall tile -600x1200
37	Wash area	Service otta and Wall tiles in following to be laid.	Otta-Granite, Wall Tile-300X600	Otta-Granite, Wall Tile-300X600	Otta-Granite, Wall Tile-300X600
38	Balconies	Wooden pattern tiles to be laid in balconies.	150x800 Size	150x800 Size	150x800 Size
39	Lift Dado	Vitrified/ceramic tiles/natural stone of size (2'x4') to be laid.OR Granite	Tile-600x1200 and frame in granite	Tile-600x1200 and frame in granite	Tile-600x1200 and frame in granite
40	Typ. Flr Entrance Lobby	Granite flooring as in staircase	Granite	Granite	Granite
41	Staircase	Granite to be used.	Granite	Granite	Granite

Door Frames, Doors & Windows					
42	Entrance Door	Door Frames and doors to be provided	**Door frame** - Wooden Door Frame, **Door** - Laminated Flush Door **Hardware** - Aldrope, tower bolt, Main Door handle and Godrej lock	**Door frame** - Teakwood Door Frame, **Door** - Laminated Flush Door **Hardware** - Aldrope, tower bolt, Main Door handle and Godrej lock	**Door frame** - Teakwood Door Frame, **Door** - Veneered Flush Door **Hardware** - Aldrope, tower bolt, Main Door handle and Godrej lock
43	Bed Room Door	Door Frames and doors to be provided	**Door frame** - Plywood frame with laminate finish **Door** - Laminated Flush Door **Hardware** - Aldrope, Bedroom Handle	**Door frame** - Plywood frame with laminate finish **Door** - Laminated Flush Door **Hardware** - Cylendrical lock	**Door frame** - Plywood frame with laminate finish **Door** - Laminated Flush Door **Hardware** - Cylendrical lock
44	Toilet, wash Area, utility Door	Door Frames and doors to be provided	**Door frame** - Granite **Door** - Laminated Flush Door **Hardware** - Aldrope, Bedroom Handle	**Door frame** - Granite **Door** - Laminated Flush Door **Hardware** - Cylendrical lock	**Door frame** - Granite **Door** - Laminated Flush Door **Hardware** - Cylendrical lock
47	Terrace Door	Door frame in MS and MS Sheet door for terrace with standard hardware.	**Door frame** -MS, **Door** - MS Sheet **Hardware** - Aldrope two side, 6" MS handle	**Door frame** -MS, **Door** - MS Sheet **Hardware** - Aldrope two side, 6" MS handle	**Door frame** -MS, **Door** - MS Sheet **Hardware** - Aldrope two side, 6" MS handle
48	Window Jambs and sills	Window jambs in Granite to be provided	one side	one side	four side
49	Windows	Windows in openings to be provided	Alunimium powder coated	Jindal, 1.2mm aluminium powder coated	UPVC Windows
50	Window grills	Designer window grills to be fixed in all windows.	as per Drawing	as per Drawing	as per Drawing
Painting Work					
51	Internal Paint	Putty, Primier & painting work to be done	Asian All protek shine	Asian Royal Luxury	Asian Royal Glitz

52	External paint	Whiting, Primier & Painting to be done	Asian Apex or equivalent	Asian Ultima or equivalent	Asian Ultima protect or equivalent
Ceiling Work					
53	Parking Area	POP in parking area to be provided	NO	Drawing Area	YES
54	Lobby Areas	POP in Lobby areas to be provided	NO	NO	YES
55	Balconies	PVC ceiling to be provided.	NO	NO	YES
Glass Railings					
56	Balconies	1050mm Height railing to be provided	MS Railing	SS Railing	Glass Railing
57	Standing Balconies	1050mm Height railing to be provided	MS Railing	SS Railing	Glass Railing

C)	**FINANCIALS**				
Sr. No	**Floor Level**	**Describtion**	**Type A**	**Type B**	**Type C**
1	Plinth Level	It includes work starting from excavation till casting of plinth slab (Slab area to be considered including verandah and entrance steps)	750	800	850
	Typical Floor Roof	It included items from above plinth level slab and below ground floor roof slab	1900	2100	2300
	Site development	It includes parking area, landscape area, all marginal spaces between plinth slab and compound wall including ramp (Includes filling materials, anti-termite treatement, slab, tiling)	475	500	550

	Water tank	Includes RCC work and waterproofing work	21	23	25
	Compound wall	Designer wall as per elevation. It excludes cladding on material like HPL on gates.	350	350	350
	Parapet Wall	Wall as per design including MS pipe work as per design (Horizontal pipe)	250	250	250
	Terrace Waterproofing	Brick bat coba on terrace level	120	120	120

Notes

• Any changes in areas and specification will be charged extra.

• The NMC building sanctioning charges or any other statutory charges for clearance of papers, etc. to be paid by owner.

• If the natural ground level is more than 18" down from road level, filling charges will be extra.

• Rates includes RCC, brickwork, plaster, internal & external paint, flooring, electrical wiring and building plumbing

• Any duct having an area below 15 sqm will not be deducted from area calculations for costing.

• Exclusions – Electronics, electrical fittings, elevation cladding materials, lift, façade materials for covering of drainage pipes & AC outdoors, fabrication work apart from grills and railing as mentioned, electric meter panel, everything not mentioned above, etc.

• GST extra as applicable.

Estimate for Semi Finished Residential Building for Mr. Aniket Deotale ji										
									Date – 06-05 25	
Sr. No	**Floor Level**	**Areas Considered**	**Type A**		**Type B**		**Type C**		**Only Civil Work**	
		(sft)	**Rate**	**Amount**	**Rate**	**Amount**	**Rate**	**Amount**	**Rate**	**Amount**
1	Plinth Level	720	750	540000	800	576000	850	612000	900	774000
2	Ground Floor Roof	1290	1900	2451000	2100	2709000	2300	2967000	900	981000
3	First Floor Roof	1290	1900	2451000	2100	2709000	2300	2967000	1050	1144500
4	Second Floor Roof	1290	1900	2451000	2100	2709000	2300	2967000	1050	1144500
5	Third Floor Roof	1290	1900	2451000	2100	2709000	2300	2967000	1050	1144500
6	Terrace Level Slab	645	1900	1225500	2100	1354500	2300	1483500	1050	1144500
7	Site development	550	475	261250	500	275000	550	302500	250	137500
8	Water tank (UG + OHT)	10000	21	21000	23	230000	25	250000	20	200000
9	Compound wall	300	350	105000	350	105000	350	105000	350	105000
10	Parapet Wall	150	250	37500	250	37500	250	37500	250	37500
11	Terrace Waterproofing	900	120	108000	120	108000	120	108000	100	90000
	Total Project Cost			**12102250**		**13522000**		**14766500**		**7270500**

Areas considered for calculation might change as per site

Office address – A4, First Floor, Khullar Apartment, Byramji Town, Nagpur-440013
Mob. No.: +91 8087088948, email id:prk@terraindstudio.com

Office address – A4, First Floor, Khullar Apartment, Byramji Town, Nagpur-440013
Mob. No.: +91 8087088948, email id:prk@terraindstudio.com